

AD-A101 248

GA1 CONSULTANTS INC MONROEVILLE PA F/6 13/13
NATIONAL DAM INSPECTION PROGRAM. BEAVER LAKE LODGE DAM (NDI I.D--ETC(U)
JUN 81 B M MIHALCIN DACW31-81-C-0015

UNCLASSIFIED

1 of 1
AL
APR 24 1988

NI

END
DATE
FILMED
8-5-8
DTIC

AD A101248

DELAWARE RIVER BASIN
RAYMONDSKILL CREEK, PIKE COUNTY

①

PENNSYLVANIA

BEAVER LAKE LODGE DAM

NDI I.D. NO. PA-00300
PENNDER I.D. NO. 52-93


LEVEL II

MR. WILLIAM B. TROY

101 E. ... / 10/10/81

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

National Dam Inspection Program. Beaver
Lake Lodge Dam (NDI I.D. Number PA-00300,
PennDER I.D. Number 52-93), Delaware Ri-
ver Basin, Raymondskill Creek, Pike
County, Pennsylvania. Phase I Inspection
Report,



DTIC
JUL 13 1981

PREPARED FOR

Productions will be in black and white.

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

DACW 31-81-C-0015

PREPARED BY

GAI CONSULTANTS, INC.
570 BEATTY ROAD
MONROEVILLE, PENNSYLVANIA 15146

JUNE 1981

DMC FILE COPY

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

81 7 10 001

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Design Flood is based on the estimated Probable Maximum Flood (greatest reasonably possible storm runoff) for the region, or fractions thereof. The Spillway Design Flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

Breach analyses are performed, when necessary, to provide data to assess the potential for downstream damage and possible loss of life. The results are based on specific theoretical scenarios peculiar to the analysis of a particular dam and are not applicable to other related studies such as those conducted under the Federal Flood Insurance Program.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

ABSTRACT

Beaver Lake Lodge Dam: NDI I.D. No. PA-00300

<u>Owner:</u>	William B. Troy
<u>State Located:</u>	Pennsylvania (PennDER I.D. No. 52-93)
<u>County Located:</u>	Pike
<u>Stream:</u>	Raymondskill Creek
<u>Inspection Date:</u>	11 November 1980
<u>Inspection Team:</u>	GAI Consultants, Inc. 570 Beatty Road Monroeville, Pennsylvania 15146

Based on a visual inspection, operational history, and hydrologic and hydraulic analysis, the dam is considered to be in poor condition.

The size classification of the facility is small and its hazard classification is considered to be significant. In accordance with the recommended guidelines, the Spillway Design Flood (SDF) for the facility ranges between the 100-year frequency flood and the 1/2 PMF (Probable Maximum Flood). Since the facility is classified near the lower bounds of the small category, the SDF is considered to be 100-year frequency flood. Results of the hydrologic and hydraulic analysis indicate the facility is not capable of passing and/or storing the inflow resulting from a 100-year frequency flood without overtopping the embankment. Consequently, the spillway system at Beaver Lake Lodge Dam is considered to be inadequate.

It is recommended that the owner immediately:

a. Develop a warning system to minimize the potential for loss of life and economic damage downstream of the facility in the event of a dam failure. The system should include provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

b. Have the spillway system assessed by a registered professional engineer experienced in the design of concrete and hydraulic structures and take remedial measures required to make the system hydraulically adequate and restore its structural integrity.

Beaver Lake Lodge Dam: NLI I.D. No. PA-00300


- c. Rehabilitate the drawdown facility and restore its operability, or provide other means for reservoir drawdown.
- d. Provide adequate erosion protection along the downstream embankment toe near the service spillway.
- e. Remove all trees and their root systems from the embankment crest and slopes and restore the grass cover.
- f. Develop formal manuals of maintenance and operations to ensure future proper care of the facility.

GAI Consultants, Inc.

Bernard M. Mihalcin
Bernard M. Mihalcin, P.E.

Approved by:

James W. Peck
JAMES W. PECK
Colonel, Corps of Engineers
Commander and District Engineer



Date 4 June 1981

Date 19 JUNE 1981

Accession For	
NTIS	CONF
DTIC	CONF
Ungraded	
For 50% per	
By	
District	
Availability Codes	
Dist	Special
A	



OVERVIEW PHOTOGRAPH

TABLE OF CONTENTS

	<u>Page</u>
PREFACE.	i
ABSTRACT	ii
OVERVIEW PHOTOGRAPH.	iv
TABLE OF CONTENTS.	v
SECTION 1 - GENERAL INFORMATION.	1
1.0 Authority.	1
1.1 Purpose.	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - ENGINEERING DATA	5
2.1 Design	5
2.2 Construction Records	6
2.3 Operational Records.	6
2.4 Other Investigations	6
2.5 Evaluation	6
SECTION 3 - VISUAL INSPECTION.	7
3.1 Observations	7
3.2 Evaluation	8
SECTION 4 - OPERATIONAL PROCEDURES	9
4.1 Normal Operating Procedure	9
4.2 Maintenance of Dam	9
4.3 Maintenance of Operating Facilities.	9
4.4 Warning System	9
4.5 Evaluation	9
SECTION 5 - HYDROLOGIC/HYDRAULIC EVALUATION.	10
5.1 Design Data.	10
5.2 Experience Data.	10
5.3 Visual Observations.	10
5.4 Method of Analysis	10
5.5 Summary of Analysis.	10
5.6 Spillway Adequacy.	11
SECTION 6 - EVALUATION OF STRUCTURAL INTEGRITY	12
6.1 Visual Observations.	12
6.2 Design and Construction Techniques	12
6.3 Past Performance	13
6.4 Seismic Stability.	13
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES.	14
7.1 Dam Assessment	14
7.2 Recommendations/Remedial Measures.	14

TABLE OF CONTENTS

APPENDIX A - VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES
APPENDIX B - ENGINEERING DATA CHECKLIST
APPENDIX C - PHOTOGRAPHS
APPENDIX D - HYDROLOGIC AND HYDRAULIC ANALYSES
APPENDIX E - FIGURES
APPENDIX F - GEOLOGY

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
BEAVER LAKE LODGE DAM
NDI NO. PA-00300, PENNDA NO. 52-93

SECTION 1
GENERAL INFORMATION

1.0 Authority.

The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

1.1 Purpose.

The purpose is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project

a. Dam and Appurtenances. Beaver Lake Lodge Dam is a nine-foot high earth embankment approximately 490 feet long, including service and emergency spillways. The facility is provided with an uncontrolled, rectangular shaped, concrete chute channel service spillway located at the right abutment, and an uncontrolled, rectangular shaped, concrete broad crested, emergency spillway located approximately 325 feet from the right abutment. The outlet works consists of a buried pipe of unknown diameter and composition located in the right abutment to the right of the service spillway. The intake structure consists of a concrete box with a manually operated sluice mechanism. The outlet end of the pipe is apparently submerged in a pool downstream of the embankment.

b. Location. Beaver Lake Lodge Dam is located on Raymondskill Creek in Milford Township, Pike County, Pennsylvania. The facility is situated about three miles southwest of the community of Milford, Pennsylvania. The dam and reservoir are contained in the Milford, Pennsylvania-New Jersey, 7.5 minute U.S.G.S. topographic quadrangle (see Figure 1, Appendix E). The coordinates of the dam are N 41° 18.0' and W74° 51.7'.

c. Size Classification. Small (nine feet high, 122 acre-foot storage capacity at top of dam).

d. Hazard Classification. Significant (see Section 3.1.e).

e. Ownership. Mr. William B. Troy
435 East 52nd Street
Apt. 7A2
New York, New York 10022

f. Purpose. Recreation.

g. Historical Data. Information contained in PennDER files indicates that Beaver Lake Lodge Dam was originally constructed prior to 1931. No design or construction details are available. In 1933, the new owner (Mr. Charles Bonoff) applied for a state permit for extensive repairs and modifications to the existing facility. The original wooden spillway was replaced with a concrete, chute channel, service spillway located at the right abutment and a concrete emergency spillway located to the left of the service spillway. The main embankment was raised by approximately one foot to increase the storage volume.

The facility has remained under control of the Bonoff family and is currently owned by Mr. William B. Troy, a relative of Mr. Charles Bonoff. Mr. Troy stated that minor repair work has been done on the dam and spillway. A full-time property manager resides near the facility.

1.3 Pertinent Data.

a. Drainage Area (square miles). 19.7

b. Discharge at Dam Site.

Discharge Capacity of the Outlet Conduit - Discharge curves are not available.

Discharge Capacity of Spillway at Maximum Pool \approx 240 cfs (see Appendix D, Sheet 7).

c. Elevations (feet above mean sea level). The following elevations were obtained through field measurements that were based on the approximate elevation of normal pool at 848.0 feet as indicated in Figure 1, Appendix E.

Top of Dam	Not known (design). 849.4 (field).
Downstream Toe of Dam	840.0 (field).
Maximum Design Pool	Not known.
Maximum Pool of Record	Not known.
Normal Pool	848.0
Service Spillway Crest	848.0
Emergency Spillway Crest	848.7
Upstream Inlet Invert	Not known.
Downstream Outlet Invert	Not known.

	Streambed at Dam Centerline	Not known.
	Maximum Tailwater	Not known.
d.	<u>Reservoir length (feet).</u>	
	Top of Dam	1300
	Normal Pool	1100
e.	<u>Storage (acre-feet).</u>	
	Top of Dam	122
	Normal Pool	101
f.	<u>Reservoir Surface (acres).</u>	
	Top of Dam	18
	Normal Pool	12
g.	<u>Dam.</u>	
	Type	Earth.
	Length	490 feet (including spillways).
	Height	Nine feet (field measured; embankment crest to downstream embankment toe).
	Top Width	Varies; 10 feet minimum to 18 feet maximum.
	Upstream slope	1.5H:1V.
	Downstream slope	Varies; 10H:1V minimum to 3H:1V maximum.
	Zoning	Not known.
	Impervious Core	Not known.
	Cutoff	Not known.
	Grout Curtain	Not known.
h.	<u>Diversion Canal and Regulating Tunnels.</u>	None.

i. Service Spillway.

Type	Uncontrolled, rectangular shaped, concrete chute channel with a triangular shaped, concrete weir.
Crest Elevation	848.0 feet.
Crest Length	35.6 feet.

j. Emergency Spillway.

	Uncontrolled, rectangular shaped, concrete chute channel with a broad crested weir.
Crest Elevation	848.7 feet.
Crest Length	38 feet (effective).

k. Outlet Conduit.

Type	Not known.
Length	Not known.
Closure and Regulating Facilities	Manually operated single sluice gate located at the the inlet (currently inoperable).
Access	The conduit control mechanism is accessible by foot along the right abutment.

SECTION 2

ENGINEERING DATA

2.1 Design

a. Design Data Availability and Sources. No design reports, calculations, or formal design data are available. PennDER files contain correspondence and photographs dating back to 1933 that provide information relative to the general history of the facility. No design or construction drawings are available from either the owner or PennDER.

b. Design Features.

1. Embankment. Based strictly on visual observations and field measurements, general statements can be made regarding the embankment design. The embankment is a nine foot high earthen structure approximately 490-feet long, including service and emergency spillways. The upstream slope is set at 1.5H:1V while the downstream slope varies from 10H:1V (minimum) to 3H:1V (maximum). A layer of riprap, partially covered by sod, protects the upstream slope. The embankment crest is generally wide, varying from 10 to 18 feet.

2. Appurtenant Structures.

a) Service Spillway. The service spillway is an uncontrolled, rectangular shaped, concrete chute channel located near the right abutment. Flows through the spillway are regulated by a triangular shaped, concrete weir, 35.6 feet long. The spillway is spanned by a small steel beamed bridge with a wood plank deck. The bridge is supported by the spillway sidewalls and a concrete pier in the center of the channel (see Photographs 1, 2, 3 and 4).

b) Emergency Spillway. The emergency spillway is located approximately 325 feet from the right abutment. It consists of a uncontrolled, rectangular shaped, concrete channel with a concrete, broad crested weir. The spillway weir has a 38-foot effective length and a 14-foot breadth.

c) Outlet Conduit. No information relative to the composition or size of the outlet conduit is available. Inlet and outlet ends of the conduit were submerged at the time of inspection and could not be observed. Originally, the conduit was used to provide flow to a turbine for electric generation. A single sluice gate operated via lever and gear mechanism was used to control the flow (see Photographs 7 and 8). The sluice gate has reportedly not been operated since the mid-1950's.

c. Specific Design Data and Criteria. No formal design data or information relative to design procedures are available.

2.2 Construction Records.

No formal construction records are available for the facility. Construction data is limited to memos and correspondence from PennDER files and a few construction photographs.

2.3 Operational Records.

No formal records of the day-to-day operation of the facility are maintained.

2.4 Other Investigations.

There are no available records concerning formal studies or investigations of Beaver Lake Lodge Dam.

2.5 Evaluation.

There is no formal information available relative to the design and construction of this facility. Information in the form of dated photographs and correspondence contained in PennDER files, in addition to information obtained during the field inspection, are considered sufficient to make a reasonable Phase I assessment of the facility.

SECTION 3

VISUAL INSPECTION

3.1 Observations.

a. General. The visual inspection of the facility suggested that the dam and its appurtenances are in poor condition.

b. Embankment. Observations made during the visual inspection indicate the embankment is in fair condition. The structure is characterized as irregular in both dimension and alignment (see Photographs 1, and 10). The downstream embankment toe is partially inundated by a small pool near the service spillway which has apparently been created for fishing purposes (see Photographs 3, 11 and 12). Some minor erosion was observed along the downstream embankment toe at the water surface near the service spillway. No significant seepage through the downstream embankment face was observed. Field measurements indicate low areas along the embankment crest to the left of the emergency spillway between 0.5 and 1.5 feet below the top of the service spillway bridge. The crest is covered with fragmented rock and grass and the slopes are covered with grass, trees and brush (see Photographs 1, 9 and 10). Trees up to 12 inches in diameter were observed along the upstream and downstream embankment slopes.

c. Appurtenant Structures.

1. Service Spillway. The service spillway is considered to be in poor condition. Excessive concrete deterioration is evident throughout the structure, particularly at the sidewalls and bridge pier. Both sidewalls and the pier are extensively spalled and cracked (see Photographs 3 and 4). Steel plates provided to protect the upstream faces of the sidewalls are becoming dislodged and corroded at normal pool level.

2. Emergency Spillway. The visual inspection revealed that the emergency spillway is in poor condition. The left half of the structure is broken and severely spalled, whereas, the right half is in fair condition (see Photograph 5). The downstream cutoff wall is in a state of disrepair and the concrete is badly deteriorated (see Photograph 6). Slight seepage under the slab and through the downstream cutoff wall was observed. Heavy weed growth was observed in the spillway forebay area. Random boulders dumped adjacent to the downstream cutoff wall have been dislodged (see Photograph 6).

3. Outlet Works. The only visible section of the outlet works is the intake structure and the control mechanism located at the right abutment (see Photographs 7 and 8). The intake structure is dilapidated and currently non-functional. The lever and gear mechanism designed to operate the sluice gate is broken.

d. Reservoir Area. The general area immediately surrounding the reservoir is composed of gentle to moderate slopes that are heavily forested. The watershed area in the immediate vicinity of the reservoir is undeveloped except for a summer cottage near the right abutment. No signs of slope distress were observed.

Several reservoirs and swamps are located within the Beaver Lake Lodge Dam watershed. Three reservoirs are located on Raymondskill Creek or its minor tributaries, and two reservoirs are located on Dwarfskill Creek, a main tributary which joins Raymondskill Creek at Lake Netimus, located approximately one mile upstream of Beaver Lake Lodge Dam. The facilities on Raymondskill Creek are known as Camp Netimus Dam, Pocono Woodland Lake Dam, and Log Tavern Pond. The facilities on Dwarfskill Creek are Crescent Lake Dam and Gold Key Lake. Log Tavern Pond and Gold Key Lake are both natural lakes with no embankments. The individual and cumulative effects of each facility upon the evaluation of Beaver Lake Lodge Dam are presented in Section 5.5.b (see Figure 2).

e. Downstream Channel. Discharges from both spillways at Beaver Lake Lodge Dam flow through a comparatively flat valley for a distance of approximately 1,500 feet, where Raymondskill Creek flows under a local road bridge. The stream has gentle to moderate side slopes in this section. The flat stream gradient combined with the steep side slopes could create backwater at the first obstruction (road bridge). Under severe storms this could inundate the dam area and the guest house located immediately on the stream bank. At a distance of approximately 2,500 feet downstream of the dam, Swale Brook merges with Raymondskill Creek. The creek then flows southwards 1,800 feet into a privately owned recreational facility known as Silver Springs Lake. Discharge from Silver Springs Lake flows into the Delaware River at a distance of 2.5 miles. In this reach the stream flows through the "Raymondskill Falls" and has very steep forested side slopes. At the junction of Highway 209 and Raymondskill Creek, a restaurant is located approximately 100 feet from the creek bank. Due to the presence of the downstream dam at Silver Springs Lake and the possibility of appreciable economic loss, as well as the potential for the loss of a few lives at the downstream structures, the hazard classification for Beaver Lake Lodge Dam is considered to be significant.

3.2 Evaluation.

The overall appearance of the facility suggests it to be in poor condition. Remedial measures are necessary to: 1) repair the deteriorated concrete spillways, 2) remove the trees and overgrowth from the embankment crest and slopes, 3) provide adequate erosion protection along the downstream embankment toe, and 4) restore the operability of the outlet conduit, or provide an alternate means of reservoir drawdown.

SECTION 4

OPERATIONAL PROCEDURE

4.1 Normal Operating Procedure.

Beaver Lake Lodge Dam is essentially a self-regulating facility. Excess inflows are automatically discharged through the uncontrolled spillways. The outlet conduit is presently non-functional and reportedly has not been operated since the mid-1950's. No formal operations manual is available.

4.2 Maintenance of Dam.

Visual observations indicate that maintenance of the dam and its appurtenant structures is presently minimal. No formal maintenance manual is available.

4.3 Maintenance of Operating Facilities.

See Section 4.2 above.

4.4 Warning System.

No formal warning system is presently in effect.

4.5 Evaluation.

Maintenance of the dam and appurtenances appears to be minimal. No means of draining the reservoir is presently available. There are no formal operations or maintenance manuals available for the facility nor is there a formal warning system in effect that could be used to notify the downstream residents should emergency conditions develop at the dam.

SECTION 5

HYDROLOGIC/HYDRAULIC EVALUATION

5.1 Design Data.

No formal design data, calculations, or reports are available. Correspondence found in PennDER files, dated 1933, indicates that state officials recommended a spillway capacity of 3,400 cfs for the reconstructed spillway.

5.2 Experience Data.

Daily records of reservoir levels and/or spillway discharges are not available. The emergency spillway is reported to discharge occasionally, although the dam has reportedly never been overtopped.

5.3 Visual Observations.

Visual observations revealed excessive deterioration of the concrete at both the service and emergency spillways. The present condition of the structures is not expected to adversely affect their operation during a flood event. However, continued deterioration could ultimately lead to the instability of these structures.

5.4 Method of Analysis.

The facility has been analyzed in accordance with the procedures and guidelines established by the U. S. Army, Corps of Engineers, Baltimore District, for Phase I hydrologic and hydraulic evaluations.

5.5 Summary of Analysis.

a. Spillway Design Flood (SDF). In accordance with procedures and guidelines contained in the National Guidelines for Safety Inspection of Dams for Phase I Investigations, the Spillway Design Flood (SDF) for Beaver Lake Lodge Dam ranges between the 100-year frequency flood and the 1/2 PMF (Probable Maximum Flood). This classification is based on the relative size of the dam (small), and the potential hazard of dam failure to downstream developments (significant). Since the facility is classified near the lower bounds of the small category, the SDF is considered to be the 100-year frequency flood.

b. Results of Analysis. Beaver Lake Lodge Dam was evaluated in order to determine if it could accommodate the 100-year frequency flood without overtopping of its embankment. The 100-

year flood peak flow was determined according to methods provided in the "Regional Frequency Study, Upper Delaware and Hudson River Basins, New York District" (see Appendix D, Sheet 4). The peak inflow under this 100-year flood event was determined to be about 3,340 cfs, while the maximum spillway capacity (at the minimum embankment crest elevation) was found to be about 240 cfs. Therefore, it can be concluded that the embankment would be overtopped under the 100-year flood event, based on the assumption of little or no attenuation of the peak inflow (no hydrograph routing was performed in this analysis; see Appendix D, Sheets 6 through 8). Also, should the embankment crest be regraded to the elevation of the top of the spillway bridge at 851.5 feet, the maximum spillway capacity would be about 1,230 cfs, and the embankment would still be subject to overtopping under the 100-year flood event.

5.6 Spillway Adequacy

As presented above, Beaver Lake Lodge Dam cannot accommodate the 100-year frequency flood (the SDF) without overtopping of its embankment. However, since its hazard category is considered to be significant, no breaching analysis was performed, in accordance with Corps directive ETL-1110-2-234. Thus, as Beaver Lake Lodge Dam cannot accommodate its SDF, its spillway is considered to be inadequate.

SECTION 6

EVALUATION OF STRUCTURAL INTEGRITY

6.1 Visual Observations.

a. Embankment. The conditions observed during the field inspection suggest the embankment is in fair condition. The following deficiencies were noted at the time of inspection and will require the owner's attention. They include:

- ° Portions of the embankment are approximately 1.5 feet below the elevation of the top of the service spillway bridge.
- ° A portion of downstream embankment toe near the service spillway is unprotected and subject to further erosion.
- ° The roots of trees growing along the upstream and downstream embankment slopes may increase the seepage potential through the embankment. Furthermore, uprooting of the trees by high winds could cause substantial volumes of the embankment material to be displaced. Hence, the trees and their root system should be removed.

b. Appurtenant Structures.

1. Service Spillway. The service spillway is in poor condition. The concrete structure is badly deteriorated, as evidenced by extensive spalling, scaling and deep structural cracking. The steel plates provided for upstream face protection are becoming dislodged and are corroded at the normal pool level. Although the spillway is functional at present, extensive repairs are necessary.

2. Emergency Spillway. The emergency spillway is in poor condition. The left half of the structure is badly deteriorated, as evidenced by extensive spalling, scaling and deep structural cracking. The downstream cutoff wall is in a state of disrepair and the dumped rock adjacent to the cutoff wall has been displaced. The approach channel is partially obstructed with heavy overgrowth in the forebay area.

3. Outlet Works. The outlet works have not been operated since the mid-1950's and the mechanism provided for operating the sluice gate is broken. The concrete walls of the intake structure are cracked and deteriorated and require repair.

6.2 Design and Construction Techniques.

No information is available that details the methods of design and/or construction.

6.3 Past Performance.

No records relative to performance history of this facility are available. The owner's representative stated, however, that the embankment had never been overtopped to his knowledge.

6.4 Seismic Stability.

The dam is located within Seismic Zone No. 1 and may be subject to minor earthquake induced dynamic forces. The facility is presently considered to be stable and it is believed that, if static conditions continue to be satisfied, the dam can withstand the expected minor dynamic forces. However, no calculations or investigations were performed to confirm this opinion.

SECTION 7

ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The results of this investigation indicate the facility is in poor condition.

The size classification of the facility is small and its hazard classification is considered to be significant. In accordance with the recommended guidelines, the Spillway Design Flood (SDF) for the facility ranges between the 100-year frequency flood and the 1/2 PMF (Probable Maximum Flood). Since the facility is classified near the lower bounds of the small category, the SDF is considered to be the 100-year frequency flood. Results of the hydrologic and hydraulic analysis indicate the facility is not capable of passing and/or storing the inflow from a 100-year frequency flood event without overtopping the embankment. Consequently, the spillway system at Beaver Lake Lodge Dam is considered to be inadequate.

b. Adequacy of Information. The available data is considered sufficient to make a reasonable Phase I assessment of the facility.

c. Urgency. The recommendations listed below should be implemented immediately.

d. Necessity for Additional Investigation. Additional investigations to assess the structural integrity of the spillway system are deemed necessary, as recommended below.

7.2 Recommendations/Remedial Measures

a. Develop a warning system to minimize the potential for loss of life and economic damage downstream of the facility in the event of a dam failure. The system should include provisions for around-the-clock surveillance during periods of unusually heavy precipitation and a communication plan with the downstream residents.

b. Have the spillway system assessed by a registered professional engineer experienced in the design of concrete and hydraulic structures and take remedial measures required to make the system hydraulically adequate and restore its structural integrity.

c. Rehabilitate the drawdown facility and restore its operability, or provide other means for reservoir drawdown.

d. Provide adequate erosion protection along the downstream embankment toe near the service spillway.

e. Remove all trees and their root systems from the embankment crest and slopes and restore the grass cover.

f. Develop formal manuals of maintenance and operations to ensure future proper care of the facility.

APPENDIX A

VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES

CHECK LIST VISUAL INSPECTION PHASE 1

NAME OF DAM Beaver Lake Lodge Dam STATE Pennsylvania COUNTY Pike
 NDI # PA — 00300 PENNDR # 52-93
 TYPE OF DAM Earth SIZE Small HAZARD CATEGORY Significant
 DATE(S) INSPECTION 11 November 1980 WEATHER Cold TEMPERATURE 28° @ 8:30 am
 POOL ELEVATION AT TIME OF INSPECTION 848.1 feet M.S.L.
 TAILWATER AT TIME OF INSPECTION Approximately 842 feet M.S.L.

INSPECTION PERSONNEL	OWNER REPRESENTATIVES	OTHERS
<u>B. M. Mihalcin</u>	<u>W. Findlay - Property Manager</u>	
<u>D. J. Spaeder</u>	<u>(Present at pre-inspection inter-</u>	
<u>K. H. Khilji</u>	<u>view only)</u>	

EMBANKMENT

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA . 00300
SURFACE CRACKS	None observed. The embankment crest appears to be covered with rock fragments and sod.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed. Area along the downstream embankment toe is inundated with backwater discharged from the service and emergency spillways.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Some erosion evident along downstream embankment toe to the left of the service spillway.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Horizontal - Curved embankment. Upstream edge is good. Crest width is irregular. Vertical - see "Profile of Dam Crest from Field Survey", Appendix A.	
RIPRAP FAILURES	No apparent riprap failures. Riprap is partially covered with sod, but, appears adequate.	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Embankment-abutment junctions are in good condition with no erosion noted. Emergency spillway sidewalls are lower than the embankment crest, but, no erosion is evident.	

EMBANKMENT

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00300
DAMP AREAS IRREGULAR VEGETA- TION (LUSH OR DEAD PLANTS)	No damp areas were observed along the downstream embankment face.	
ANY NOTICEABLE SEEPAGE	None through the downstream embankment face. Slight seepage observed beneath the floor slab of emergency spillway - not significant.	
STAFF GAGE AND RECORDER	None.	
DRAINS	None observed.	
VEGETATION	Upstream edge of embankment crest is lined with trees and shrubs. Five large maple trees (\approx 12 inches in diameter) are situated near the service spillway. Many sizeable pine trees were observed along the downstream embankment face.	

OUTLET WORKS

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA · 00300
INTAKE STRUCTURE	Concrete sluice mechanism located at the right abutment. Concrete walls are cracked and deteriorated.	
OUTLET CONDUIT (CRACKING AND SPALLING OF CON- CRETE SURFACES)	Buried and inundated pipe - not observed. Outlet conduit had been formerly used to operate an electric generator. Generator house has since been dismantled. Exact location of outlet discharge is not known at present.	
OUTLET STRUCTURE	None observed. Outlet is probably submerged in the pool along the downstream embankment toe.	
OUTLET CHANNEL	Discharges into the tailwater pool along the downstream embankment toe.	
GATE(S) AND OPERA- TIONAL EQUIPMENT	Single sluice gate located at the outlet conduit inlet to the right of the service spillway. Operation of the gear mechanism is manual by lever. Reported, the conduit has not been operated since the mid-1950's.	

EMERGENCY SPILLWAY

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00300
TYPE AND CONDITION	Uncontrolled, rectangular shaped, concrete channel with a broad crested, concrete overflow weir. Poor condition. Severe spalling and cracking observed along the weir.	
APPROACH CHANNEL	Rock lined. Approach area is obstructed by thick grass-like vegetation in the spillway forebay immediately adjacent to the upstream face of the overflow weir.	
SPILLWAY CHANNEL AND SIDEWALLS	Channel floor (weir) in poor condition with severe spalling and cracking evident particularly along its left side. Downstream cutoff wall in disrepair with slight leakage evident. Spillway sidewalls are in fair condition.	
STILLING BASIN PLUNGE POOL	Small boulder filled basin located immediately beyond the weir.	
DISCHARGE CHANNEL	Rock lined, natural channel - unobstructed.	
BRIDGE AND PIERS EMERGENCY GATES	None.	

SERVICE SPILLWAY

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDIN PA - 00300
TYPE AND CONDITION	Uncontrolled, rectangular shaped, concrete chute channel with a triangular shaped weir. Overall condition is poor.	
APPROACH CHANNEL	Rock lined - unobstructed.	
OUTLET STRUCTURE	N/A.	
DISCHARGE CHANNEL	The spillway discharges into a small pool that inundates the area along the downstream embankment toe. Spillway discharges may be causing the minor erosion observed along the downstream embankment toe to the left of the service spillway.	
CHANNEL FLOOR AND SIDEWALLS	Downstream end of channel floor is cracked and possibly undercut and in poor condition. Concrete sidewalls are severely spalled as is the center bridge pier.	
BRIDGE AND PIERS	Steel beamed bridge with a wood deck in good condition. As previously stated however, the spillway sidewalls and bridge pier that support the structure are in poor condition.	

INSTRUMENTATION

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA • 00300
MONUMENTATION SURVEYS	None observed.	
OBSERVATION WELLS	None.	
WEIRS	None.	
PIEZOMETERS	None.	
OTHERS	None.	


RESERVOIR AREA AND DOWNSTREAM CHANNEL

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00300
SLOPES: RESERVOIR	Gentle to moderate slopes that are heavily forested.	
SEDIMENTATION	None apparent.	
DOWNSTREAM CHANNEL (OBSTRUCTIONS, DEBRIS, ETC.)	Channel passes through the local road culverts between Beaver Lake Lodge Dam and Silver Spring Lake located about 4500 feet downstream.	
SLOPES: CHANNEL VALLEY	Gentle stream gradient set in a partially wooded valley with gentle to moderate confining slopes between dam and Silver Spring Lake. Channel slope becomes steep and valley narrows downstream of Silver Spring Lake.	
APPROXIMATE NUMBER OF HOMES AND POPULATION	Significant hazard - potential for appreciable economic loss. (see Section 3.1.e).	

NOT # PA - 00300

BEAVER LAKE LODGE DAM

PROFILE OF DAM CREST
FROM FIELD SURVEY



SCALE:

VERTICAL: 1 IN = 4 FT
HORIZONTAL: 1 IN = 100 FT

SUBJECT: BEAVER LAKE LODGE DAM
BY: DLD DATE: 5-11-81 SHEET NO. 1 OF 1
CHKD BY: DLD DATE: 5-11-81 PROJECT NO. 80-258-300

APPENDIX B
ENGINEERING DATA CHECKLIST

**CHECK LIST
ENGINEERING DATA
PHASE I**

NAME OF DAM Beaver Lake Lodge Dam

ITEM	REMARKS	NDI# PA- 00300
PERSONS INTERVIEWED AND TITLE	William Findlay - Property Manager (since 1957) - resides at the site and is employed by the owner, William B. Troy of New York, New York.	
REGIONAL VICINITY MAP	See Figures 1 and 2, Appendix E.	
CONSTRUCTION HISTORY	Built prior to 1931.	
AVAILABLE DRAWINGS	None available. Several drawings contained in PennDER files do not even remotely depict as-built conditions and are considered to be useless.	
TYPICAL DAM SECTIONS	None available.	
OUTLETS: PLAN DETAILS DISCHARGE RATINGS	None available.	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA - 00300
SPILLWAY: PLAN SECTION DETAILS	None available.	
OPERATING EQUIP. MENT PLANS AND DETAILS	Sluice gate (lever operated) with outlet pipe buried in right abutment. Apparently discharges into pool downstream of spillway, although its discharge end was not observed.	
DESIGN REPORTS	None available.	
GEOLOGY REPORTS	None available.	
DESIGN COMPUTATIONS: HYDROLOGY AND HYDRAULICS STABILITY ANALYSES SEEPAGE ANALYSES	None available.	
MATERIAL INVESTIGATIONS: BORING RECORDS LABORATORY TESTING FIELD TESTING	None available.	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA - 00300
BORROW SOURCES	Not known.	
POST CONSTRUCTION DAM SURVEYS	None.	
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None.	
HIGH POOL RECORDS	Reportedly the Dam has never been overtopped. Emergency spillway reportedly discharges on occasion.	
MONITORING SYSTEMS	None.	
MODIFICATIONS	Minor repairs only.	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA - 00300
PRIOR ACCIDENTS OR FAILURES	None.	
MAINTENANCE: RECORDS MANUAL	None.	
OPERATION: RECORDS MANUAL	None.	
OPERATIONAL PROCEDURES	Self-regulating.	
WARNING SYSTEM AND/OR COMMUNICATION FACILITIES	None presently. Caretaker knew several downstream residents.	
MISCELLANEOUS		

GAI CONSULTANTS, INC.

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

NDI ID # PA-00300
PENNDER ID # 52-93

SIZE OF DRAINAGE AREA: 2.4 square miles (local); 19.7 square miles (total).

ELEVATION TOP NORMAL POOL: 848.0 STORAGE CAPACITY: 101 acre-feet.

ELEVATION TOP FLOOD CONTROL POOL: - STORAGE CAPACITY: -

ELEVATION MAXIMUM DESIGN POOL: - STORAGE CAPACITY: -

ELEVATION TOP DAM: 849.4 STORAGE CAPACITY: 122 acre-feet.
(field).

SPILLWAY DATA

CREST ELEVATION: 848.0 feet (service); 848.7 feet (emergency).

TYPE: Uncontrolled, rectangular, concrete channels (service & emergency).

CREST LENGTH: 35.6 feet (service); 38 feet (emergency).

CHANNEL LENGTH: 25 feet (service); 14 feet (emergency).

SPILOVER LOCATION: Right abutment (service); near left abutment (emergency).

NUMBER AND TYPE OF GATES: None.

OUTLET WORKS

TYPE: Size and composition of conduit is not known.

LOCATION: Right of the service spillway.

ENTRANCE INVERTS: Not known.

EXIT INVERTS: Not known.

EMERGENCY DRAWDOWN FACILITIES: Single sluice gate at inlet.

HYDROMETEOROLOGICAL GAGES


TYPE: None.

LOCATION: -

RECORDS: -

MAXIMUM NON-DAMAGING DISCHARGE: Not known.

APPENDIX C
PHOTOGRAPHS



**BEAVER LAKE LODGE DAM
PHOTOGRAPH KEY MAP**

PHOTOGRAPH 1 View across the embankment crest looking towards the left abutment.

PHOTOGRAPH 2 View showing the entry channel of the service spillway.

PHOTOGRAPH 3 View of the service spillway looking upstream. Note the broken bottom slab.

PHOTOGRAPH 4 View of the service spillway showing deterioration of concrete pier and sidewall.



2



1



PHOTOGRAPH 5 View of emergency spillway looking towards the right abutment. Note the brush growth in the entry channel.

PHOTOGRAPH 6 View of the downstream end of the emergency spillway. Note the erosion and broken cutoff wall.

PHOTOGRAPH 7 View of intake structure (inoperable sluice gate). Note broken concrete wall.

PHOTOGRAPH 8 View of the sluice gate lever and gear mechanism (inoperable).




6



8



5



7

PHOTOGRAPH 9 View of the upstream embankment face.

PHOTOGRAPH 10 View of the embankment crest looking towards left abutment. Note the trees on upstream and downstream faces.

PHOTOGRAPH 11 View showing undercutting of the downstream slope of the embankment near the service spillway.

PHOTOGRAPH 12 View of the pool along the downstream toe of the embankment.



10



12



9



11

APPENDIX D
HYDROLOGIC AND HYDRAULIC ANALYSES

SUBJECT DAM SAFETY INSPECTION
BEAVER LAKE LARGE DAM
BY DJS DATE 3-31-81 PROJ. NO. 80-238-300
CHKD. BY DLB DATE 5-11-81 SHEET NO. 1 OF 8



DAM STATISTICS

HEIGHT OF DAM = 9 FT (FIELD MEASURED - TOP OF DAM TO
DOWNSTREAM EMBANKMENT TOE; "TOP OF DAM" HERE AND ON ALL
SUBSEQUENT CALCULATION SHEETS REFERS TO THE LOW AREA IN THE
EMBANKMENT CREST.)

NORMAL POOL STORAGE CAPACITY = 33×10^6 GALLONS
= 101 AC-FT (SEE NOTE 1)

MAXIMUM POOL STORAGE CAPACITY = 122 AC-FT (SHEET 3)
(@ TOP OF DAM)

DRAINAGE AREA:

<u>SUBAREA</u>	<u>LOCAL D.A. (SQ. MI.)</u>	<u>CUMULATIVE D.A. (SQ. MI.)</u>
GOLD KEY LAKE	1.5	—
CRESCENT LAKE	4.6	6.1
LOG TOWER LAKE	0.8	—
BROWN WOODLAND LAKE	0.3	—
CAMP NEVINUS LAKE	10.1	17.3
BEAVER LAKE	2.4	19.7

(PLANNETTERED IN USGS TOPO QUADS - MILFORD, EXETER, NH,
AND SHOHOLA, PA)

NOTE 1: OBTAINED FROM WATER RESOURCES INVENTORY FORM,
BEAVER LAKE DAM, ID # 90-52-93, FOUND IN FLOOD DEPT
FILES.

SUBJECT DAM SAFETY INSPECTION

BEAVER LAKE LODGE DAM

BY DJS DATE 4-1-81 PROJ. NO. 80-238-300

CHKD. BY DLB DATE 5-11-81 SHEET NO. 2 OF 8



Engineers • Geologists • Planners
Environmental Specialists

ELEVATIONS:

TOP OF DAM (DESIGN)	=	UNKNOWN
TOP OF DAM (FIELD)	=	849.4
NORMAL POOL	=	848.0
SERVICE SPILLWAY CREST	=	848.0
EMERGENCY SPILLWAY CREST	=	848.7
UPSTREAM INLET INVERT (DESIGN)	=	UNKNOWN
DOWNSTREAM OUTLET INVERT (DESIGN)	=	UNKNOWN
DOWNSTREAM OUTLET INVERT (FIELD)	=	UNKNOWN
DOWNSTREAM EMBANKMENT TOE (FIELD)	=	840.0
STREAMBED @ DAM CENTERLINE	=	UNKNOWN

(USGS TOPO QUAD - MILFORD, VT)

DAM CLASSIFICATION

DAM SIZE: SMALL (REF 1, TABLE 1)

HAZARD CLASSIFICATION: SIGNIFICANT (FIELD OBSERVATION)

REQUIRED SDF: 100 YEAR FLOOD TO 1/2 PMF (REF 1, TABLE 3)

SELECTED SDF = 100-YEAR FLOOD.

SUBJECT

DAM SAFETY INSPECTIONBEAVER LAKE LODGE DAM

BY

DJS

DATE

5-7-81

PROJ. NO.

80-238-300

CHKD. BY

DLB

DATE

5-11-81

SHEET NO.

3OF 8Engineers • Geologists • Planners
Environmental SpecialistsRESERVOIR CAPACITYRESERVOIR SURFACE AREAS:

- SURFACE AREA (S.A.) @ NORMAL POOL (EL. 848.0) = 12 ACRES
- S.A. @ EL. 860.0 = 61 ACRES

(PLANIMETERED ON USGS TOPO QUAD - MILFORD, PA)

- S.A. @ TOP OF DAM (EL. 849.4) = 17.7 ACRES

(BY LINEAR INTERPOLATION)

VOLUME @ NORMAL POOL = 101 AC-FT (SEE SHEET 1)

- CALCULATE VOLUME @ TOP OF DAM:

USING THE MODIFIED PRISMATOIDAL RELATIONSHIP

$$\Delta V_{1-2} = \frac{h}{3} (A_1 + A_2 + \sqrt{A_1 \cdot A_2}) \quad (\text{REF. 14, P. 15})$$


WHERE ΔV_{1-2} = INCREMENTAL VOLUME BETWEEN ELEVATIONS 1 + 2, IN AC-FT, h = ELEVATION 1 - ELEVATION 2, IN FT, A_1 = S.A. @ ELEV 1, IN AC., A_2 = S.A. @ ELEV 2, IN AC.

AT ELEV. 849.4,

$$\begin{aligned} \text{VOLUME} &= 101 + \frac{1.4}{3} (12 + 17.7 + \sqrt{12 \times 17.7}) \\ &= \underline{122} \text{ AC-FT.} \end{aligned}$$

 \therefore STORAGE CAPACITY @ TOP OF DAM = 122 AC-FT.

SUBJECT DAM SAFETY INSPECTION
BEAVER LAKE LODGE DAM
BY DJS DATE 5-7-81 PROJ. NO. 80-238-300
CHKD. BY DLB DATE 5-11-81 SHEET NO. 4 OF 8



100-YEAR FLOOD COMPUTATION

THE FOLLOWING DATA AND METHODOLOGY WERE TAKEN FROM
THE "REGIONAL FREQUENCY STUDY, UPPER DELAWARE AND HUDSON
RIVER BASINS, NEW YORK DISTRICT," PREPARED FOR THE NEW YORK
DISTRICT, CORPS OF ENGINEERS BY THE HYDROLOGIC ENGINEERING
CENTER, DAVIS, CALIFORNIA, NOVEMBER 1974.

COMPUTE THE 100-YEAR FLOOD PEAK FOR BEAVER
LAKE LODGE DAM:

1) COMPUTE MEAN LOG OF ANNUAL PEAK DISCHARGES:

$$\log(Q_m) = C_m + 0.87 \log(A)$$

WHERE Q_m = GEOMETRIC MEAN OF ANNUAL FLOOD PEAKS, IN CFS,
 C_m = MAP COEFFICIENT,
 A = DRAINAGE AREA = 19.7 SQUARE MILES (SHEET 1).

FROM FIG 2, "REGIONAL FREQUENCY STUDY,"

$$C_m = 1.6$$

$$\begin{aligned}\therefore \log(Q_m) &= 1.6 + 0.87 \log(19.7) \\ &= 2.726\end{aligned}$$

2) COMPUTE STANDARD DEVIATION:

$$S = C_s - 0.05 \log(A)$$

WHERE S = STANDARD DEVIATION OF LOGARITHMS OF ANNUAL PEAKS,
 C_s = MAP COEFFICIENT FOR STANDARD DEVIATION.

SUBJECT DAM SAFETY INSPECTION
BEAVER LAKE LODGE DAM
 BY DJS DATE 5-7-81 PROJ. NO. 80-238-300
 CHKD. BY DLB DATE 5-11-81 SHEET NO. 5 OF 6



FROM FIG. 3, "REGIONAL FREQUENCY STUDY,"

$$C_s = 0.34$$

$$\therefore S = 0.34 - 0.05 \log (19.7) \\ = 0.275$$

3) COMPUTE 100-YEAR FLOOD PEAK:

$$\log (Q(P)) = \log (Q_m) + K(P, g) \cdot S$$

WHERE $\log (Q(P))$ = LOG. OF ANNUAL FLOOD PEAKS FOR A GIVEN EXCEEDANCE FREQUENCY (P),

$\log (Q_m)$ = MEAN LOG. OF ANNUAL FLOOD PEAKS,

$K(P, g)$ = MAGNITUDE IN STANDARD DEVIATIONS FROM MEAN FOR A GIVEN EXCEEDANCE FREQUENCY PERCENTAGE (P) AND SKEW COEFFICIENT (g).

S = STANDARD DEVIATION OF LOGS OF ANNUAL FLOOD PEAKS.

FROM FIG. 5, "REGIONAL FREQUENCY STUDY,"

$$g = +0.8.$$

FOR 100-YEAR EVENT, $P = 1.0$ PERCENT

FROM TABLE 10, "REGIONAL FREQUENCY STUDY,"

$$K(1.0, 0.8) = 2.90$$

$$\therefore \log (Q_1) = 2.726 + (2.90)(0.275) \\ = 3.5235$$

$$Q_1 = \underline{\underline{3340}} \text{ CFS} = 100\text{-YR FLOOD PEAK.}$$

SUBJECT DAM SAFETY INSPECTION

BEAVER LAKE LODGE DAM

BY DJS DATE 5-8-81 PROJ. NO. 80-238-200


CHKD. BY DLB DATE 5-11-81 SHEET NO. 6 OF 8



Engineers • Geologists • Planners
Environmental Specialists


SPILLWAY CAPACITY

1.) SERVICE SPILLWAY



(NOT TO SCALE)

2.) EMERGENCY SPILLWAY



EFFECTIVE CREST LENGTH = 38 FT

(NOT TO SCALE)

- SKETCHES BASED ON FIELD SURVEY.

THE SERVICE SPILLWAY CONSISTS OF A RECTANGULAR SHAPED CONCRETE CHUTE CHANNEL, WITH DISCHARGES REGULATED BY A TRIANGULAR SHAPED WEIR. THE EMERGENCY SPILLWAY CONSISTS OF BROAD-CRESTED CONCRETE WEIR WHICH DISCHARGES INTO A ROCK-LINED CHANNEL.

SUBJECT DAM SAFETY INSPECTION
BEAVER LAKE LODGE DAM
BY DSS DATE 5-8-81 PROJ. NO. 80-238-300
CHKD. BY DLB DATE 5-11-81 SHEET NO. 7 OF 8



DISCHARGE OVER EACH OF THE WEIRS CAN BE ESTIMATED
BY THE RELATIONSHIP

$$Q = CLH^{3/2} \quad (\text{REF 5, p. 5-3})$$

WHERE Q = DISCHARGE, IN CFS,
 C = COEFFICIENT OF DISCHARGE,
 L = WEIR LENGTH, IN FT.,
 H = HEAD, IN FT.

ASSUME THAT THE DISCHARGE COEFFICIENT IS ON THE ORDER OF 3.0
FOR THE SERVICE SPILLWAY AS WELL AS FOR THE EMERGENCY SPILLWAY
(REF 5, TABLES 5-5 - 5-7).

AT EL. 849.4 (MIN. ELEVATION ALONG EMBANKMENT CREST),

$$\begin{aligned} Q_{\text{TOTAL}} &= Q_{\text{SERVICE}} + Q_{\text{EMERGENCY}} \\ &= (3.0)(35.6)(849.4 - 848.0)^{3/2} + (3.0)(38.0)(849.4 - 848.7)^{3/2} \\ &= \underline{240 \text{ CFS}} \end{aligned}$$

AT EL. 851.5 (TOP OF SPILLWAY BRIDGE),

$$\begin{aligned} Q_{\text{TOTAL}} &= (3.0)(35.6)(3.5)^{3/2} + (3.0)(38)(2.8)^{3/2} \\ &= \underline{1230 \text{ CFS}} \end{aligned}$$

SUBJECT DAM SAFETY INSPECTION
BEAVER LAKE LODGE DAM
BY DJS DATE 5-8-81 PROJ. NO. 80-238-300
CHKD. BY DLB DATE 5-11-81 SHEET NO. 8 OF 8



IN COMPARING THE 100-YR FLOOD PEAK (3340 CFS) WITH THE TOTAL SPILLWAY CAPACITY AT THE TOP OF THE DAM (240 CFS) IT IS SEEN THE DAM WILL BE OVERTOPPED BY THE 100-YEAR FLOOD. IF THE EMBANKMENT CREST WERE REGRADED TO THE ELEVATION OF THE TOP OF THE SPILLWAY BRIDGE (EL 851.5), THE MAXIMUM SPILLWAY CAPACITY WOULD BE ABOUT 1230 CFS, AND THE DAM WOULD STILL BE SUBJECT TO OVERTOPPING UNDER THE 100-YEAR EVENT. IT WAS ASSUMED HERE THAT THERE WOULD BE NO SIGNIFICANT ATTENUATION OF THE 100-YEAR FLOOD, IN SPITE OF THE FACT THAT THERE ARE UPSTREAM DAMS AND NATURAL LAKES. THIS ASSUMPTION WAS BASED ON THE FACT THAT THERE WAS LITTLE OR NO ATTENUATION OF FLOOD PEAKS AT THE UPSTREAM CRESCENT LAKE DAM (SEE NOTE 2). SINCE CAMP NEVINUS DAM (FIG. 2) AND BEAVER LAKE LODGE DAM ARE APPROXIMATELY IN THE SAME SIZE RANGE AS CRESCENT LAKE DAM, IT CAN BE ASSUMED THAT THERE WOULD BE NO SIGNIFICANT ATTENUATION OF THE FLOOD PEAKS AT THESE FACILITIES. ALSO, ALTHOUGH GOLD KEY LAKE AND LOG TAVERN POND (FIG. 2) ARE NATURAL LAKES WITH LARGE STORAGE CAPACITIES, THESE FACILITIES ARE LOCATED IN THE UPPEMOST REACHES OF THE WATERSHED, AND THUS WILL HAVE LITTLE EFFECT ON THE PEAK FLOWS ENTERING BEAVER LAKE. FINALLY, POCOMO WOODLAND LAKE DAM (NDI No. PA-00443, DER No. 52-179), FOR WHICH A PHASE I INSPECTION REPORT IS CURRENTLY BEING PREPARED, HAS A RELATIVELY SMALL DRAINAGE AREA (0.3 SQUARE MILES; SEE FIG. 2), AND THIS WILL HAVE LITTLE EFFECT ON BEAVER LAKE INFLOWS. THEREFORE, IT IS CONCLUDED THAT BEAVER LAKE LODGE DAM WILL BE OVERTOPPED UNDER THE 100-YEAR EVENT.

NOTE 2: FROM "PHASE I INSPECTION REPORT, NATIONAL DAM INSPECTION PROGRAM, CRESCENT LAKE DAM," NDI No. PA-00413, DER No. 52-143, PREPARED BY ELSASSER ASSOCIATES, INC., HARRISBURG, PA, JUNE 1973.

LIST OF REFERENCES

1. "Recommended Guidelines for Safety Inspection of Dams," prepared by Department of the Army, Office of the Chief of Engineers, Washington, D. C. (Appendix D).
2. "Unit Hydrograph Concepts and Calculations," by the U. S. Army, Corps of Engineers, Baltimore District (L-519).
3. "Seasonal Variation of Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours," Hydrometeorological Report No. 33, prepared by J. T. Reidel, J. F. Appleby and R. W. Schloemer, Hydrologic Service Division, Hydrometeorological Section, U. S. Army, Corps of Engineers, Washington, D. C., April 1956.
4. Design of Small Dams, U. S. Department of the Interior, Bureau of Reclamation, Washington, D. C., 1973.
5. Handbook of Hydraulics, H. W. King, and E. F. Brater, McGraw-Hill, Inc., New York, 1963.
6. Standard Handbook for Civil Engineers, F. S. Merritt, McGraw-Hill, Inc., New York, 1963.
7. Open-Channel Hydraulics, V. T. Chow, McGraw-Hill, Inc., New York, 1959.
8. Weir Experiments, Coefficients, and Formulas, R. E. Horton, Water Supply and Irrigation Paper No. 200, Department of the Interior, United States Geological Survey, Washington, D. C., 1907.
9. "Probable Maximum Precipitation, Susquehanna River Drainage Above Harrisburg, Pennsylvania," Hydrometeorological Report No. 40, prepared by H. V. Goodyear and J. T. Riedel, Hydrometeorological Branch Office of Hydrology, U. S. Weather Bureau, U. S. Department of Commerce, Washington, D. C., May, 1965.
10. Flood Hydrograph Package (HEC- 1) Dam Safety Version, Hydrologic Engineering Center, U. S. Army, Corps of Engineers, Davis, California, July 1978.
11. "Simulation of Flow Through Broad Crest Navigation Dams with Radial Gates," R. W. Schmitt, U. S. Army, Corps of Engineers, Pittsburgh District.
12. "Hydraulics of Bridge Waterways," BPR, 1970, Discharge Coefficient Based on Criteria for Embankment Shaped Weirs, Figure 24, page 46.

13. Applied Hydraulics in Engineering, H. M. Morris and J. N. Wiggert, Virginia Polytechnic Institute and State University, 2nd Edition, The Ronald Press Company, New York, 1972.
14. Standard Mathematical Tables, 21st Edition, The Chemical Rubber Company, 1973, page 15.
15. Engineering Field Manual, U. S. Department of Agriculture, Soil Conservation Service, 2nd Edition, Washington, D. C., 1969.
16. Water Resources Engineering, R. K. Linsley and J. B. Franzini, McGraw-Hill, Inc., New York, 1972.
17. Engineering for Dams, Volume 2, W. P. Creager, J. D. Justin, J. Hinds, John Wiley & Sons, Inc., New York, 1964.
18. Roughness Characteristics of Natural Channels, H. H. Barnes, Jr., Geological Survey Water-Supply Paper 1849, Department of the Interior, United States Geological Survey, Arlington, Virginia, 1967.
19. "Hydraulic Charts for the Selection of Highway Culverts," Hydraulic Engineering Circular No. 5, Bureau of Public Roads, Washington, D. C., 1965.

APPENDIX E

FIGURES

LIST OF FIGURES

<u>Figure</u>	<u>Description/Title</u>
1	Regional Vicinity Map
2	Watershed Boundary Map

FIGURE 1

REGIONAL VICINITY MAP

----- LONGEST WATERCOURSE
⊙ CENTROID OF DRAINAGE AREA

Watershed Boundary



1000 2000 FEET




FIGURE 2

WATERSHED BOUNDARY MAP

APPENDIX F

GEOLOGY

Geology

Beaver Lake Lodge Dam is located in the glaciated Low Plateaus section of the Appalachian Plateaus physiographic province of eastern Pennsylvania. In this area, the Appalachian Plateaus province is characterized topographically by flat-topped, hummocky hills formed as a result of glaciation and subsequent stream dissection of nearly flat-lying strata. The Devonian age sedimentary rock strata in Pike County regionally strike N35°E and dip gently to the northwest. The Delaware River is the major drainage basin in the area. Major tributary streams intersect the Delaware River at right angles; whereas, smaller streams display a slightly more random tributary pattern. Both major and minor tributary stream systems are joint controlled and exhibit modified rectangular and trellis-type drainage patterns.

Structurally, the area containing Pike County lies on the south flank of a broad, asymmetrical synclinorium that plunges to the southwest. Superimposed on this broad structural basin are numerous anticlinal and synclinal folds characterized by planar limbs and narrow hinges. Due to prior glaciation, low relief and surficial soil cover, fold axes are difficult to trace.


The sedimentary rock sequences in the vicinity of the dam and reservoir are probably members of the Susquehanna Group of Upper Devonian age (see Geology Map). The sedimentological changes observed in the Catskill Formation indicate that the rate of sedimentation exceeded the rate of basin subsidence, resulting in a facies change from marine to non-marine strata. On the accompanying geology map the delineation between the Middle and Upper Devonian age sedimentary rock sequences represents the Allegheny Front, which separates the Valley and Ridge physiographic province from the Appalachian Plateaus physiographic province.

Approximately half of Pike County, including the dam site, is covered by a blanket of Wisconsin age (most recent) glacial drift which, based on the degree of weathering, was probably deposited during the Woodfordian stage. Valley bottoms are typically covered by recent alluvium and Woodfordian outwash of variable thickness, but typically less than 10 feet. These deposits are characteristically unconsolidated stratified sand and gravel, usually with more gravel than sand and some small boulders. The direction of the Wisconsin ice advance was from the northeast over the Catskill Mountains and from the north over the Appalachian Plateau. The terminal moraine resulting from the southern most advance of the Wisconsin ice sheet in this area is located in the southern portion of Monroe County, which borders Pike County to the South.

References:

1. Fletcher, F. W., Woodrow, D. L., "Geology and Economic Resources of the Pennsylvania Portion of the Milford and Port Jervis 15 minute U.S.G.S. Topographic Quadrangles," Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 223, 1970.

2. Sevon, W. D., Berg, T. M., "Geology and Mineral Resources of the Skytop Quadrangle, Monroe and Pike Counties, Pennsylvania", Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 214A., 1978.
3. Sevon, W., Personal Communication, Commonwealth of Pennsylvania Department of Environmental Resources, Harrisburg, December 3, 1980.



LEGEND

UPPER DEVONIAN



SUSQUEHANNA GROUP

Catskill Formation - Shohola Member - interbedded with a few feet thick beds of greenish-grey to greyish and very fine to medium-grained sandstone, and sandy shale and thin-bedded fine-grained sandstone and shale. Sandstone and shale are predominantly low-rank micaceous, but in some thin-bedded sandstone may have simple or planar beds of sandstone to medium-grained, generally coarse-grained sandstone, and some with shale units and abruptly disconformable to gradational. Sandstone are generally fine to medium-grained, finely laminated and well-sorted. Mud cracks, convolute bedding, and other marks of primary deformation are common with sandstone units. Member is more than 1,000 feet thick. Lower contact is gradational, and is marked at top of highest bed of the underlying Anaconia. Anaconia is a thin member, mostly composed of silty, micaceous, finely laminated well-sorted shale containing thin beds of thin-bedded sandstone and silty very fine grained sandstone. This is the "first well" in the sequence in exposure, and is about 100 feet thick. Lower contact is gradational and is marked at the base of the first bed of the Delaware River Flats Member, grayish-green, micaceous, laminated sandstone and shale, and is marked by a thin shale. Beds range from a few inches to as much as 1 foot thick. Sandstone are low-rank micaceous and contain no marine fossils. Member is about 500 feet thick. Lower contact is gradational.

MIDDLE DEVONIAN




HAMILTON GROUP

Mahantango Formation - Upper member - medium-dark grey, fine to medium grained, thin-bedded sandstone and silty shale; member is about 100 feet thick and is separated from lower member by the "Barnet fault", a calcareous silty shale bedstone containing abundant barnacles. The "Barnet fault" is about 100 feet thick, lower member, virtually same lithology as upper member. But is about 1,000 feet thick. Lower contact is gradational.

Marcellus Shale - Dark-grey, evenly laminated, silty shale, and silty shale. It is a very hard, micaceous and is well-sorted, bedding is generally diagonal. Member is about 100 feet thick. Lower contact is gradational.

SCALE



REFERENCE:

GEOLOGIC MAP OF NORTHEASTERN PENNSYLVANIA COMPILED BY GEO. W. STOSE AND O.A. LUJUNGSTEDT COMMONWEALTH OF PENNSYLVANIA DEPT. OF INTERNAL AFFAIRS DATED 1932 SCALE 1" = 5 MILES.

GEOLOGY MAP



